



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institute under Ministry of Human Resource Development, Govt. of India)
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,
Mangalam B.O., Tirupati – 517 507, Andhra Pradesh, India.

No. 06/IISER/TIRUPATI/2017-18

Dated 31/01/2018

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below up to **3.00 PM on 08/02/2018** from approved and eligible contractors registered with CPWD, Andhra Pradesh State PWD, Railways, MES in appropriate category for Civil/ (B&C) works. The quotations will be opened at 3.30 PM on the same day.

Name of Works: Providing laminated plywood partition in IISER Tirupati transit campus

Issue to —

Name and address of the agency —


Assistant Engineer (Civil)
IISER TIRUPATI

Terms and Conditions:

- 1) The applicant should be registered with CPWD , Andhra Pradesh State PWD, MES, Railways, state universities in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the registration certificate along with the quotation.
- 2) Time period for completion of work shall be 15 days from the date of placing the work order by IISER .
- 3) Quotation can be obtained from IISER TIRUPATI office Building between 10 AM to 4 PM on all working days before date of submission.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3.00 PM on 08/02/2018 on above mentioned address. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ .The bid shall be submitted in the original bid document (as issued by the IISER) super scribing the name of work.

- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER Tirupati.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 9) The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. No advance payment shall be made by IISER Tirupati.
IT, WCT and other applicable taxes and cess will be deducted from the bills as of the work.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati whenever specification CPWD/ IS specification are not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 12) Agency to submit measurement and abstract sheets to IISER Tirupati for payments.


Assistant Engineer (Civil)

IISER Tirupati

Encl : - Schedule of Quantity (BOQ) — As per Annexure A

Sign & stamp of Agency

Annexure A

Name of work : Providing laminated plywood partition in IISER Tirupati transit campus					
NIQ NO : 06/IISER/TIRUPATI/2017-18					
Item No	Description of Item	Qty	Unit	Rate	Amount
1	Providing & Fixing decorative high pressure laminated sheet of plain /wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.. Quoted rate shall be including tools & tackles, lead, lift, taxes, etc. Nothing extra shall be paid seperately.				
	1 mm thk	75	Sqm		
2	Providing and fixing 8 mm thick BWR plywood conforming to IS: 1328 , plywood confirming IS : 303 marked, wall panelling with screws and fittings wherever required etc complete, Quoted rate shall be including all taxes duties , lead , lift etc. Noting extra shall be paid separately.	75	Sqm		
3	Providing and fixing aluminium section conforming to IS: 733 and IS: 1285, as for framing in partition walls. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle all complete as per architectural drawings and the directions of Engineer-in-charge. Quoted rate shall be including all taxes duties , lead , lift, etc. Noting extra shall be paid seperatly.				
	Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC 15)	150	kg		
Total					