



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति  
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI  
(An Autonomous Institute under Ministry of Human Resource Development, Govt. of India)  
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,  
Mangalaml B.O., Tirupati – 517 507, Andhra Pradesh, India.

No. 05/IISER/TIRUPATI/2017-18

Dated 24/01/2018

**NOTICE INVITING QUOTATION**

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below up to **3.00 PM** on **01/02/2018** from approved and eligible contractors registered with CPWD, Andhra Pradesh State PWD, Railways, MES in appropriate category for Civil/ (B&C) works. The quotations will be opened at 3.30 PM on the same day.

**Name of Works:** Renovation of old kitchen area near academic building at IISER  
Tirupati transit campus

Issue to —

Name and address of the agency —

  
Assistant Engineer (Civil)  
IISER TIRUPATI

**Terms and Conditions:**

- 1) The applicant should be registered with CPWD , Andhra Pradesh State PWD, MES, Railways, state universities in appropriate category for Civil/ (B & C) works. The registration certificate should be valid till the last date of receipt of tender. Applicant should submit attested or notarized copies of the registration certificate along with the quotation.
- 2) Time period for completion of work shall be 30 days from the date of placing the work order by IISER .
- 3) Quotation can be obtained from IISER TIRUPATI office Building between 10 AM to 4 PM on all working days before date of submission.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3.00 PM on 01/02/2018 on above mentioned address. Quotation received after the date & time specified above shall not be accepted. Any delays , postal delay etc. will not be entertained. Agency should quote for all the items in the in the BOQ .The bid shall be submitted in the original bid document (as issued by the IISER) super scribing the name of work.

- 5) Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear including acceptance of all terms and conditions of this Quotation by the agency. IISER reserves the right to accept or reject the quotation/s without assigning any reasons.
- 6) Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER Tirupati.
- 7) Quoted rates should be inclusive of cost of all the materials, labour cost , all taxes, octroi , duties , cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid separately.
- 8) All approved makes shall be as specified in BOQ and as per CPWD specifications agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 9) The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. No advance payment shall be made by IISER Tirupati.  
IT, WCT and other applicable taxes and cess will be deducted from the bills as of the work.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati whenever specification CPWD/ IS specification are not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws.
- 12) Agency to submit measurement and abstract sheets to IISER Tirupati for payments.

  
Assistant Engineer (Civil)  
IISER Tirupati

Encl : - Schedule of Quantity (BOQ ) — As per Annexure A

Sign & stamp of Agency

## Annexure A

<b>Name of work : Renovation of old kitchen area near academic building at IISER Tirupati transit campus</b>					
<b>NIQ NO : 05/IISER/TIRUPATI/2017-18</b>					
Item No	Description of Item	Qty	Unit	Rate	Amount
1	Making openings of required size for exhaust fan in brick wall with necessary lintel arrangement wherever required and finishing the same with proper plastering as instructed by the engineer in charge. Quoted rate shall be including tools & tackles, lead, lift, taxes, etc. Nothing extra shall be paid seperately.	5	each		
2	Wall painting with acrylic emulsion paint over exisiting painted wall, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved color,brand and manufacture, including scraping of existing coat of paint and applying additional coats wherever required, to achieve even shade, color and finish. Quoted rate shall be including tools & tackles, lead, lift, taxes, etc. Nothing extra shall be paid seperately.				
	one or more coat	150	Sqm		
3	Laying thermal insulation of ceiling (Under deck insulation) held in position by GI mesh as directed by the engineer in charge. (Only Insulation material will be provided by the institute rest including fully galvanized chicken mesh & accessories required shall be arranged by the contractor). Quoted rate shall be including tools & tackles, screws, lead, lift, taxes, etc. Nothing extra shall be paid seperately.	105	Sqm		
4	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including making the existing floor ready for laying tile by removal of exisiting flooring wherever required, grouting the joints with white cement and matching pigments etc, complete.Quoted rate shall be including tools & tackles, lead, lift, taxes, etc. Nothing extra shall be paid seperately. (Approved make : Kajaria/somany/similar)				
	one or more coat	25	Sqm		

Item No	Description of Item	Qty	Unit	Rate	Amount
5	<p>Providing and Fixing 15 mm thick false ceiling tiles of approved texture &amp; make of size 595 x 595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening"for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge. (Approved make : Armstrong biogaard) Quoted rate shall be including tools &amp; tackles, accessories, lead, lift, taxes, etc. Nothing extra shall be paid seperately.</p>	105	Sqm		
				<b>Total</b>	