

CORRIGENDUM -I

Dated 08.10.2020.

**Name of Work: Supply Installation Testing and Commissioning of 625 KVA DG set at IISER Tirupati Main Campus, Jangalapalli Village, Yerpedu Mandal, Chittoor Dist.**

**Tender No: IISERT/Engg/ Elec/02 dated 03.10.2020**

**Pre-Bid Meeting Minutes uploaded on 08.10.2020.**

S.No	Clause No. / Page No.	Existing	To be Read as
1	Notice Inviting e-Tender , Page 3	Estimate Cost Put to Bid (Rs.) Rs 44,33,08/-	Estimate Cost Put to Bid (Rs.) Rs 44,33,083/-
2	Site Tests / Manufacture site test - Technical Spec 54 (b)	Site Tests Load Test 50% load 15 Minutes 100% load 15 Minutes 110% load 15 Minutes  Manufacturer's Site  Full Load test for 1 Hr Over Lad test @110% for 1 Hr  Diesel for Testing to be supplied by IISER.	1. Load test as per standard norms of 12 hours on 100% load and 1 hour on 110% load to be carried out at Manufacturer/Supplier works to be witnessed by IISER representatives before dispatch. 2. The Load , Diesel etc are under the scope of the bidder. All bidders may quote accordingly. The visit to Manufacturers/suppliers place for witnessing is subject to restrictions in movement by concerned authorities. However, the testing is mandatory.
3	Vol II ; Clause 1.5.1	Warranty of the DG set	Warranty is in the scope of Bidder for the Defect Liability Period of one year. Assistance of OEM to be ensured by the Bidder.
4	Scope	-	CEA Clearance for the work in the scope of Bidder.
5	Section I , NIT clause 1	Period of Completion: 3 weeks	Period of Completion : 5 weeks



*D. V. Narayana Rao*  
 08/10/2020  
 Superintending Engineer  
 IISER Tirupati