

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH (IISER) , TIRUPATI

Name of Work: Construction of Parking Shed, Canteen, Security Cabin and other Civil Works at IISER Tirupati Permanent Campus, Yerpedu Mandal, Tirupati.

Tender No: 05/IISERT/Engg/2021-22 dated 10.01.2022

The Following are the clarifications against queries from various bidders through online:

S.No	Item No.	Query	Clarification
1	BOQ Item no. 50	Providing and fixing glass strips in joints of terrazzo/ cement concrete floors 40 mm wide and 4 mm thick – Clarification for UNIT for item no. 50	It is clarified that the Unit of Item No. 50 should be read as ‘m’ against ‘sqm’
2	BOQ item no. 58	Design, Supply and Installation of assembly of co-extruded UV protected 18 mm thick multi-layered panels incorporated into a complete system. Panels shall have six layers in translucent combination to achieve required Lux levels. Panels shall be with grip-lock notch standing seam running lengthwise to accommodate the connectors. Panel system shall be assembled & installed on MS Structure (paid separately) with 3 numbers self-drilling screws & trapezoid SS fasteners to ensure a pull-out load of min. 7000N (7KN) tested as per ISO 6892:1998 and IS 1608: 2005	Design, Supply and Installation of assembly of co-extruded UV protected 18 mm thick multi-layered panels(Polycarbonate sheets) incorporated into a complete system. Panels shall have six layers in translucent combination to achieve required Lux levels. Panels shall be with grip-lock notch standing seam running lengthwise to accommodate the connectors. Panel system shall be assembled & installed on MS Structure (paid separately) with 3 numbers self-drilling screws & trapezoid SS fasteners to ensure a pull-out load of min. 7000N (7KN) tested as per ISO 6892:1998 and IS 1608: 2005
3	BOQ item no. 60	Providing and Fixing 15mm C.P. brass Two way Bib cock (for health faucet) with wall flange and C.P copper connecting pipe 450 mm long nut and rubber, washer with C.P. brass flange complete, including cutting and making good the walls, wherever required (Jaquar) – Model no. clarification	It is clarified that the Model no. for the Jaquar series is FLR-CHR-5041N
4	Financial Bid	Rates to be Quoted in Financial Bid with GST?	The rates should be quoted inclusive of GST i.e. 12% for the works contract.

These clarification shall be read along with BoQ and rates quoted shall be for full item including clarifications furnished here with.

P V Nayanadas