



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH d

(An Autonomous Institute under Ministry of Human Resource Development, Govt. of India)
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,
Mangalam B.O., Tirupati – 517 507, Andhra Pradesh, India.

NIQ No:08/IISER/Tirupati/NIQ/2019-20

Date: 27.12.2019

Notice Inviting Quotation

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below upto 3:00 PM on 02/01/2020 from approved and eligible contractors registered with CPWD, State PWD, Railways, MES or Reputed agencies with similar works experience. One work should be executed with direct with Central or state Government organization. The quotations will be opened at 3.30 PM on the same day

Name of work: - Aluminium partition work in IISER Tirupati transit campus.

Issue to –

Address of the agency –



Terms and Conditions:

- 1) As per mentioned criteria agencies should submit attested or notarized copies of the valid certificates along with quotation.
- 2) No advance payment shall be made by IISER Tirupati.
- 3) Time period for completion of work shall be **7 Days** from the date of placing the confirm order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on maintenance@iisertirupati.ac.in or submit to IISER Tirupati office in hard copy on all working days before a day of submission date of quotation.
- 4) Blank Quotations can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/> .
- 5) All agencies need to submit their quotation in hard copy in sealed cover so as to reach the office on or before 3 PM on 02/01/2020. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as uploaded by the IISER, Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e.,02/01/2020 at 3.30 PM in the presence of bidder or their authorized representatives, if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions of this tender by the firm. IISER reserves the right to accept or reject all the quotations without assigning any reasons.

- 6) Quoted rates should be inclusive of cost of all the materials, labour cost, GST, octroi , duties, cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 8) The successful agency shall make his own arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 9) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 10) Security deposit @2.5% shall be deducted from RA Bills. The same shall be released after satisfactory completion of 6 Months DLP from the date of handing over.
- 11) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/ IS specification are not available.
- 12) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 13) Agency to submit computerized measurement and abstract sheets to IISER Tirupati for payments.
- 14) Amount quoted for items should be as specified in the BOQ.


Executive Engineer
IISER Tirupati



Sign & stamp of Agency-

Encl : - Schedule of Quantity – As per Annexure A.

Annexure A

Name of Work : Aluminium partition work in IISER Tirupati transit campus					
Item No	Description of Item	Qty	UNIT	RATE	AMOUNT
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
a	For Fixed Portion : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	250.00	kg		
b	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) - Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	60.00	kg		
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade 1 Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides	50.00	sqm		
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm)	7.00	sqm		
4	Providing and fixing 150mm long tower bolts with SS screws etc; complete as per direction of Engineer-in-charge.	6.00	Nos		
5	Providing and fixing aluminium tubular handle, Anodized (AC 15) Aluminium Tubular handle bar etc; complete as per direction of Engineer-in-charge	6.00	Nos		
6	Supply & fixing of door Stoppers with SS screws etc; complete as per direction of Engineer-in-charge.	3.00	Nos		
7	Providing and fixing Brass 100mm mortice latch and locks with 6 leaves wiithour pair of handles(best make of approved quality) for alluminium doors including necessary cutting and making good etc; complete:	3.00	Nos		
8	Supplying and fixing of 6" Hinges including all tools, accessories and labour charges etc; complete:	9.00	Nos		
Total					

