



# भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institute under Ministry of Human Resource Development, Govt. of India)  
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,  
Mangalam B.O., Tirupati – 517 507, Andhra Pradesh, India.

NIQ No: 7/IISER/Tirupati/NIQ/2020-21

Date: 02.02.2021

## Notice Inviting Quotation

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below upto 3:00 PM on 09/02/2021 from eligible contractors agencies with similar works experience. The quotations will be opened at 3.30 PM on the same day.

**Name of work: Providing PUF panel wall partition in IISER Tirupati Transit campus**

Issue to –

Address of the agency –



*V. Srujan*  
02/02/21  
Executive Engineer  
IISER Tirupati

### **Terms and Conditions:**

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Time period for completion of work shall be **10 Days** from the date of placing the confirm order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on [srujan@iisertirupati.ac.in](mailto:srujan@iisertirupati.ac.in) or submit to IISER Tirupati office in hard copy on all working days before a day of submission date of quotation.
- 3) Blank Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 09/02/2021. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 09/02/2021 at 3.30 PM in the presence of bidder or their authorized representatives, if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons.
- 5) Quoted rates should be inclusive of cost of all the materials, labour cost, octroi , duties, cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid.

- 6) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 7) The successful agency shall make his own arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 11) Agency to submit computerized measurement and abstract sheets to IISER Tirupati for payments.
- 12) Amount quoted for items should be as specified in the BOQ.
- 13) Following the latest developments and restrictions imposed in the country and state in view of the COVID-19, the agency should have strict compliance towards the rules and precautionary measures mentioned in the orders issued by the State Government from time to time. The submission of bids should be in the tender box placed at main gate of Institute. Also, successful agency should ensure all safety precautions, social distancing norms during the execution of work.



*V. Srinivasan*  
Executive Engineer  
IISER Tirupati

Sign & stamp of Agency-

Encl : - Schedule of Quantity – As per Annexure A.

Annexure A

S.No.	Description of items	Qty	Unit	Rate	Amount
1	Providing and installation of pre painted galvalume steel (PPGL) non-corrugated Wall Panel: 50 mm double skin demountable panel made of 0.47 mm thick PPGL sheet on both side with PUF infill of 40 Kg/m <sup>3</sup> density, food grade with sealant for seamless and airtight finish, Shade shall be approved by the engineer in charge. The rate is inclusive of all taxes, tools, tackles, labour, etc. Nothing extra shall be paid.	53	Sqm		
2	Providing and installation of Coving R80 aluminium coving wall to wall, wall to ceiling, wall to floor, the shade of coving shall be approved by the engineer in charge. The rate is inclusive of all taxes, tools, tackles, labour, etc. Nothing extra shall be paid.	85	m		
3	Supply and installation of 45 mm thick Single shutter door made of 0.8 mm thick GI powder coated sheet on both sides with infill of PUF 40 kg/m <sup>3</sup> . Door frame will be 1.2 mm thick GI powdercoated sheet. All hardware like D Handle, Dead lock, Flush bolt, Door closer, Hinges, Automatic door drop seal and etc. Size: 1000 x 2100 mm. The rate is inclusive of all taxes, tools, tackles, labour, etc. Nothing extra shall be paid.	2	Nos		
<b>Total</b>					

*V. Srinivasan*

