



# भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

## INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institute under Ministry of Education, Govt. of India)  
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,  
Mangalam B.O., Tirupati – 517 507, Andhra Pradesh, India.

NIQ No: 04/IISER/Engg/NIQ/2021-22

Date: 20.07.2021

### Notice Inviting Quotation

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below up to 3:00 PM on 27/07/2021 from eligible contractors / agencies with similar works experience. The quotations will be opened at 3.30 PM on the same day.

**Name of work: Supply & laying of Firefighting line at IISER Tirupati Main Campus, Yerpedu, Tirupati.**

### **Terms and Conditions:**

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Agency should have experience in Fire Fighting related works. The proof of the similar work experience or experience certificate should be submitted along with the quotation. **Agency must visit the site before quoting the NIQ for better understanding.**
- 3) Time period for completion of work shall be **10 Days** from the date of placing the confirm order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on [engineering@iisertirupati.ac.in](mailto:engineering@iisertirupati.ac.in) or submit to IISER Tirupati office in hard copy on all working days before a day of submission date of quotation. Blank Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 27/07/2021. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 27/07/2021 at 3.30 PM in the presence of bidder or their authorized representatives, if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons.
- 5) Security Deposit of 2.5% will be withheld in the Contractor's bill which will be released after successful completion of defect liability period of 6 months.

*V. Ramesh Kumar*





- 6) Quoted rates should be inclusive of cost of all the materials, labour cost, octroi, duties, cost of sample and fees towards testing of materials in labs, royalties etc. complete. Nothing extra shall be paid.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 8) The successful agency shall make his own arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 9) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/ IS specification are not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 12) Agency to submit computerized measurement and abstract sheets to IISER Tirupati for payments.
- 13) Amount quoted for items should be as specified in the BOQ.
- 14) Following the latest developments and restrictions imposed in the country and state in view of the COVID-19, the agency should have strict compliance towards the rules and precautionary measures mentioned in the orders issued by the State Government from time to time. The submission of bids should be in the tender box placed at main gate of Institute. Also, successful agency should ensure all safety precautions, social distancing norms during the execution of work.

  
Executive Engineer  
IISER Tirupati



Sign & stamp of Agency-

Encl: - Schedule of Quantity – As per Annexure A.

<b>BOQ</b>					
<b>Name of Work:- Supply &amp; laying of Firefighting line at IISER Tirupati Main Campus, Yerpedu, Tirupati</b>					
Sr.No	Item Description	Unit	Qty	Rate	Amount
1	Providing, laying, testing and commissioning of Class 'C' heavy duty MS Pipe conforming to IS 1239/3589 including fittings, elbows, tees flanges, tapers, nuts bolts, gaskets etc. fixing the pipe on the wall/ceiling/Floor with suitable clamps and Cement Concrete block as per requirement and painting with two or more coats of synthetic enamel paint of required shade complete as required.(Internal) <b>Make : Jindal or TATA</b>				
1.1	100 mm dia	Metre	50.00		
2	Supplying and Fixing single headed Stainless Steel internal hydrant valve with instantaneous Stainless Steel couplings of 63 mm dia with cast iron wheel ISI marked conforming to IS 5290 (Type-A) with blank cap and chain as required . <b>Brand: SUPERX (or) Equivalent</b>	Each	2.00		
3	Supplying and fixing 63 mm dia , 15 mtr long RRL hose pipe with 63 mm dia Male and Female Gun metal / SS couplings duly binded with GI wire, rivets etc. conforming to IS 636 (type A) as required. <b>Brand: SUPERX (or) Equivalent</b>	Each	2.00		
4	Supplying & fixing 63 mm dia Stainless Steel branch pipe with 20mm (nominal internal diameter) size Gun Metal nozzle conforming to IS 903, suitable for instantaneous connection to interconnect hose pipe coupling as required. <b>Brand: SUPERX (or) Equivalent</b>	Each	2.00		
5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality(screwed end) : 25 mm dia <b>Brand: SUPERX (or) Equivalent</b>	Each	2.00		
6	Supplying and Fixing First-Aid Hose Reel with MS construction spray painted in Post office red, conforming to IS 884 with upto date amendments, complete with the following as required. <b>Brand: SUPERX (or) Equivalent</b>				
6.1	30 MTR long 20 mm (nominal internal) dia water hose Thermoplastic (Textile reinforced) Type -2 as per IS: 12585				
	20 MM (nominal internal) dia gun metal globe valve and nozzle.				
	Drum and brackets for fixing the equipment on wall.				
	Connections from riser with 25 m dia stop valve(gun metal) & M.S. Pipe	Set	2.00		
7	Supply & Fixing of double door hose box with lock & key for provision to keep 2 nos 15 mt length hose and 1 nos branch pipe with nozzle	Each	2.00		
	<b>Total</b>				

Total Amount in words :

