



भारतीयविज्ञानशिक्षाएवंअनुसंधानसंस्थानतिरुपति
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institute under Ministry of Education, Govt. of India)
Transit Campus : Sree Rama Engineering College Campus, Karakambadi Road,
Mangalam B.O., Tirupati – 517 507, Andhra Pradesh, India.

NIQ No: 09/IISER/Engg/NIQ/2020-21

Date:03.03.2021

Notice Inviting Quotation

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Tirupati for the work mentioned below upto 3:00 PM on 10/03/2021 from eligible contractors /agencies with similar works experience. The quotations will be opened at 3.30 PM on the same day.

Name of work: Removal of shrubs & grass in the ground and external leveling around Plant Science lab at IISER Tirupati, Main Campus .

Issue to –

Address of the agency –



Terms and Conditions:

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Agency should have similar work experience.
- 3) Time period for completion of work shall be **10 Days** from the date of placing the confirm order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on srujan@iisertirupati.ac.in or submit to IISER Tirupati office in hard copy on all working days before a day of submission date of quotation.
- 4) Blank Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>
- 5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 10/03/2021. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 10/03/2021 at 3.30 PM in the presence of bidder or their authorized representatives, if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons.



- 6) Quoted rates should be inclusive of cost of all the materials, labour cost, octroi , duties, cost of sample and fees towards testing of materials in labs ,royalties etc. complete. Nothing extra shall be paid.
- 7) All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 8) The successful agency shall make his own arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 9) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/ IS specification are not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 12) Agency to submit computerized measurement and abstract sheets to IISER Tirupati for payments.
- 13) Amount quoted for items should be as specified in the BOQ.
- 14) Following the latest developments and restrictions imposed in the country and state in view of the COVID-19, the agency should have strict compliance towards the rules and precautionary measures mentioned in the orders issued by the State Government from time to time. The submission of bids should be in the tender box placed at main gate of Institute. Also, successful agency should ensure all safety precautions, social distancing norms during the execution of work.



Sign & stamp of Agency-

Encl : - Schedule of Quantity – As per Annexure A.

Annexure A

Name of Work : Removal of shrubs & grass in the ground and external leveling around Plant Science lab at IISER Tirupati Main Campus.					
NIQ No. 09/IISER/Engg/NIQ/2020-21					
S.No.	Description of works	Unit	Qty	Rate	Amount
1	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared. All kinds of soil	sqm	6833		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	cum	216		
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	cum	349		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1 :4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	cum	3.3		
Total					



