



NIQ No: 11/IISER/Tirupati/NIQ/2024-25

Date:29.10.2024

**NOTICE INVITING QUOTATION**

Item rate sealed quotation are invited by the undersigned on behalf of Director IISER Tirupati for the following work.

Sl. No	Name of Work	Time period of contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1	Removing & shifting of Electrical Items from transit campus to IISER Tirupati Permanent Campus.	07 Days	29.10.2024	04.11.2024 at 03:00 p.m.	04.11.2024 at 03:30 p.m.

Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>

**TERMS AND CONDITIONS**

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Applicants quoting for this work should have valid GST registration with similar work experience and also the documentary proof for similar work experience should be submitted along with the quotation, without the proof of similar work experience the bids will be summarily rejected.
- 3) Agency must visit the site before quoting the NIQ for better understanding.
- 4) Time period for completion of work shall be **07 (Seven) Days** from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on [engineering@iisertirupati.ac.in](mailto:engineering@iisertirupati.ac.in) or submit to the IISER Tirupati office in hard copy on all working days before a day of the submission date of quotation.
- 5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 04 /11/2024. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 04/11/2024 at 3.30 PM in the presence of Bidder or their authorized

*V. Jayaram*





भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति  
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)

Permanent Campus: Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
Tirupati, Andhra Pradesh – 517 619.

representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons/conditions.

- 6) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.
- 7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) **Security deposit @ 2.5 %** shall be recovered at source and refunded after satisfactory completion of **DLP of (06) six months**.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/IS specification is not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.



**Executive Engineer (E), IISER Tirupati**  
On behalf of Director IISER, Tirupati

Copy to:

1. The Registrar, IISER Tirupati.
2. Deputy Registrar F & A.
3. Assistant Engineer Electrical.



**SCHEDULE OF QUANTITIES**

**Name of the Work:** Removing & shifting of Electrical Items from transit campus to IISER Tirupati Permanent Campus.

S.No	Item Description	Unit	Qty	Rate	Amount
1	Removing & shifting of circuit/sub main of the following sizes of FRLS PVC insulated copper conductor, single core cable from existing floor raceway/DLP trunking & conduit etc as required. The agency is responsible for the removal and shifting of the material from transit to the permanent campus IISER Tirupati and must Ensure that premises areas are protected during removal also, the agency has to rectify any major damages caused during removal. The Rate includes all taxes, loading, and unloading. The agency has to prepare a statement for payment and the same has to be certified by the respective engineer.				
1.1	3R X 1.5 sq. mm	metre	300.00		
1.2	3R X 2.5 sq. mm	metre	1000.00		
1.3	3R X 4.0 sq. mm	metre	5000.00		
2	The following DLP UPVC trunking U-PVC to Off-White thickness 2.0mm for the base and sides with removable covers including removing of required accessories etc. as required. The agency is responsible for the removal and shifting of the material from transit to the permanent campus IISER Tirupati and must ensure that premises areas are protected during removal also, the agency has to rectify any major damages caused during removal. The Rate includes all taxes, loading, and unloading. The agency has to prepare a statement for payment and the same has to be certified by the respective engineer.				
2.1	100 X50 mm DLP UPVC trunking with base and cover	metre	1000.00		
2.2	150 X50 mm DLP UPVC trunking with base and cover	metre	50.00		
3	Removing & shifting of 2pole enclose & 2Pole MCB connections to be removed properly.( <b>The agency has to take care of the premises while removing the material</b> )	Each	200.00		

*(Handwritten Signature)*





# भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

## INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)

Permanent Campus: Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
Tirupati, Andhra Pradesh – 517 619.

S.No	Item Description	Unit	Qty	Rate	Amount
4	Removing & shifting of 12Way /8 Way VTPN DBs along with Incoming & outgoing MCBS of the respective distribution boards connections to be removed.(The agency has to take care of the premises while removing the material)	Job	8.00		
5	Removing & shifting of Ceiling fans along with down rod from respective rooms and necessary connections to be removed. <b>(The agency has to take care of the premises while removing the material)</b>	Each	150.00		
6	Removing & shifting of Wall fans from respective rooms along with required accessories etc. <b>(The agency has to take care of the premises while removing the material)</b>	Each	20.00		
7	Removing & shifting of Cat 6 LAN Cable in existing floor raceway as required. <b>(The agency has to take care of the premises while removing the material)</b>	metre	5000.00		
8	Removing & shifting of following split AC Units from labs/office rooms from transit campus to Permanent campus store room. Rate is inclusive of all taxes, transportation, loading & unloading etc. Nothing extra shall be paid.				
8.1	1.5 Ton Split AC Unit	Each	20.00		
8.2	2 Ton Split AC Unit	Each	15.00		
9	Removing & shifting The following modular cover plate & PVC back box long with switch & sockets 6/16amps to be removed from 100x50mm DLP UPVC trunking/wall with required accessories etc. The agency is responsible for the removal and shifting of the material from transit to the permanent campus IISER Tirupati and must Ensure that premises areas are protected during removal also, the agency has to rectify any major damages caused during removal. The Rate includes all taxes, loading, and unloading. The agency has to prepare a statement for payment and the same has to be certified by the respective engineer.				
9.1	2 Modular Switch Board (1 No 10/6A Amps Switch & socket)	Each	100.00		



*V. Jayaraman*





भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति  
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)  
Permanent Campus: Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
Tirupati, Andhra Pradesh – 517 619.

S.No	Item Description	Unit	Qty	Rate	Amount
9.2	3 Modular Switch Board (1 No of 6/16 Amps Switch & socket)	Each	100.00		
9.3	4 Modular Switch Board (1 No of 6/16 Amps Switch & socket)	Each	100.00		
9.4	6 Modular Switch Board (2 No of 6/16 Amps Switch & socket)	Each	500.00		
9.5	8 Modular Switch Board (2 No of 6/16 Amps Switch & 3 Nos of socket)	Each	500.00		
10	Removing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. (Transportation from transit campus to permanent campus store room). Rate inclusive of all taxes etc. Nothing extra shall be paid.				
10.1	Upto 35 sq. mm	metre	500.00		
10.2	Upto 35 sq. mm to 95 Sqmm	metre	100.00		
<b>Total (Rs.)</b>					

**Total Amount in Words:**

**Note:** - Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

*V. Ramesh Kumar* 29/10/24

**Executive Engineer (E), IISER Tirupati**  
On behalf of Director IISER, Tirupati  
(To be filled by the Agency)



**Signature of the bidder** :  
**Name of the Agency** :  
**Mobile Number & E-mail ID** :  
**Correspondence Address** :