



NIQ No: 09/IISER/Tirupati/NIQ/2024-25

Date:30.09.2024

**NOTICE INVITING QUOTATION**

Item rate sealed quotation are invited by the undersigned on behalf of Director IISER Tirupati for the following work.

Sl. No	Name of Work	Time period of contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1	Removing of Split AC units, trunking, and cables from Academic building transit campus and Re-installation in IISER Tirupati permanent campus, Yerpedu, Tirupati.	10 Days	30.09.2024	07.10.2024 at 03:00 p.m.	07.10.2024 at 03:30 p.m.

Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>

**TERMS AND CONDITIONS**

- 1) No advance payment shall be made by IISER Tirupati.
- 2) **Applicants quoting for this work should have valid GST registration with similar work experience and also the documentary proof for similar work experience should be submitted along with the quotation, without the proof of similar work experience the bids will be summarily rejected.**
- 3) **Agency must visit the site before quoting the NIQ for better understanding.**
- 4) Time period for completion of work shall be **10 (Ten) Days** from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on [engineering@iisertirupati.ac.in](mailto:engineering@iisertirupati.ac.in) or submit to the IISER Tirupati office in hard copy on all working days before a day of the submission date of quotation.
- 5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 07/10/2024. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 07/10/2024 at 3.30 PM in the presence of bidder or their authorized





representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons/conditions.

- 6) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.
- 7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) **Security deposit @ 2.5 %** shall be recovered at source and refunded after satisfactory completion of **DLP of (06) six months**.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/IS specification is not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.

*V. Ranga Ganesh*  
30/7/20

**Executive Engineer (E), IISER Tirupati**  
On behalf of Director IISER, Tirupati



Copy to:

1. The Registrar, IISER Tirupati.
2. Deputy Registrar F & A.
3. Assistant Engineer Electrical.



# भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

**INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI**

(An Autonomous Institution of Ministry of Education, Govt. of India)

Permanent Campus: Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
Tirupati, Andhra Pradesh – 517 619.

## SCHEDULE OF QUANTITIES

**Name of the Work:** Removing of Split AC units, trunking, and cables from Academic building transit campus and Re-installation in IISER Tirupati permanent campus, Yerpedu, Tirupati.

S.No	Item Description	Unit	Qty	Rate	Amount
1	Removing & shifting of 1.5 Ton Split AC units from labs/office rooms from transit campus to Permanent campus store room. Rate is inclusive of all taxes, transportation, loading & unloading etc. Nothing extra shall be paid.	Each	20.00		
2	Removing & shifting of 2 Ton Split AC unit from Guest House rooms from transit campus to Permanent campus store room. Rate is inclusive of all taxes, transportation, loading & unloading etc. Nothing extra shall be paid.	Each	5.00		
3	Removing & shifting of 100x50 mm DLP UPVC trunking U-PVC to Off-White thickness 2.0mm for the base and sides with removable covers including fixing of required accessories nothing extra shall be paid.	metre	300.00		
4	Removing & shifting of 6/8 modular cover plate along with pvc back box to be fixed on 100x50mm DLP UPVC trunking, including fixing of necessary switch & sockets 6/16amps capacity suitable on the modular boxes, with required accessories etc. as required.	Each	500.00		
5	Fixing & overall servicing with water/foam wash for Indoor & out door coils of following Split AC units in Research block at respective floors at IISER Tirupati, Main campus. Rate is inclusive of all taxes.				
5.1	1.5 Ton Split AC Unit	Each	20		
5.2	2 Ton Split AC Unit	Each	10		
6	supply & fixing of refrigerant suction piping using Copper pipes for split AC units along with rubber insulation applying of ribbon tape etc as required. nothing extra shall be				
6.1	1.5 Ton Split AC Unit	Each	45		
6.2	2 Ton Split AC Unit	Each	15		
7	supply & fixing of heavy-duty type outdoor unit stands for split AC units along with necessary accessories etc as required.	Each	10		
8	Supply & fixing of 4 core x 4 sq. mm flexible Copper control cabling		100		





# भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति

## INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)

Permanent Campus: Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
Tirupati, Andhra Pradesh – 517 619.

S.No	Item Description	Unit	Qty	Rate	Amount
	saddles from indoor to outdoor unit connection as required.				
9	Providing core cut on RCC walls size of 100mm dia for different locations at IISER Tirupati, Main Campus.	Each	4		
10	Supply & filling of Gas charging for 1.5 Ton AC unit at required locations as required .	Each	5		
11	Removing & shifting of 3runs x4 Sqmm/3 runs x 2.5 Sqmm copper wire from the existing conduit in common rooms transit campus hostel to Permanent campus store room. Rate is inclusive of all taxes, transportation loading & unloading etc. Nothing extra shall be paid.	metre	1000		
<b>Total</b>					

### Total Amount in Words:

**Note:** - Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

*V. Srinivasan*  
30/9/24

**Executive Engineer (E), IISER Tirupati**

On behalf of Director IISER, Tirupati

(To be filled by the Agency)



**Signature of the bidder** :

**Name of the Agency** :

**Mobile Number & E-mail ID** :

**Correspondence Address** :