

**SPOT QUOTATION**

**03/IISER/Tirupati/Spot Quotations/2025-2026**

**Date: 10.07.2025.**

Sealed quotations are invited on behalf of the Director IISER, Tirupati from the **“Registered Civil Contractor”** in CPWD/ AP state PWD/ MES/ Railways/ Autonomous bodies, or an agency with valid GST registration, for the work **“Providing and Fixing of Galvanised Roof Shed for RO Plant on Terrace of Academic Research Building, IISER Tirupati Campus, Yerpedu.”** to the undersigned on or before 3 pm on 10/07/2025.

The quotations will be opened on 11/07/2025 at 3:30 pm.

**Schedule of Quantities**

S.NO	Description of Item	units	Qty	Rate	Amount
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
1.1	Hot finished welded type tubes	kg	850.00		
2	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns' epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters	sqm	101.00		

S.NO	Description of Item	units	Qty	Rate	Amount
	and trusses and including cutting to size and shape wherever required.				
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade				
3.1	Two or more coats on new work	sqm	45.00		
4	Providing and laying factory made Precast concrete solid blocks of 200 mm thickness of grade M10 made of C&D waste from approved manufacturer in superstructure above plinth level up to floor V level				
4.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	3.00		
5	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing.				
5.1	1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1.50		
6	Centering and shuttering including strutting, propping etc. and removal of form work for				
6.1	Columns, piers, abutments, pillars, posts and struts	sqm	13.00		
7	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) finished rough with sponge.	sqm	32.00		



**भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति**  
**INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI**  
 (An Autonomous Institution of Ministry of Education, Govt. of India)  
 Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,  
 Tirupati, Andhra Pradesh – 517 619..

S.NO	Description of Item	units	Qty	Rate	Amount
8	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade				
8.1	New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	sqm	32.00		

Total (in words) \_\_\_\_\_

**Terms and Conditions:**

1. No advance payment shall be made by IISER Tirupati.
2. The work shall be carried out within **15 Days** from the receipt of work order.
3. Specification for the work to be carried out as per Schedule of quantities.
4. Your rates quoted should be inclusive of all taxes, GST, freight, levis, duties, octroi, royalties, etc. However, no price escalation or adjustment and mobilization advance is payable.
5. Proof of registration has to be submitted along with the quotation, **failing to submit relevant documents will lead to rejection of the quotation.**

Agency with seal



Assistant Engineer (C)

Executive Engineer  
 IISER, Tirupati

(To be filled by agency)

Name of the Agency :  
 PAN number :  
 GSTIN :  
 Mobile Number & E-mail ID :  
 Correspondence Address :

Copy to:

1. The Registrar office, IISER Tirupati for information.
2. Joint Registrar F&A.