

NOTICE INVITING QUOTATION

Item rate sealed quotation are invited by the undersigned on behalf of Director, IISER Tirupati for the following work.

Sl. No	Name of Work	Time period of contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1.	Provision of RO Water Line Connection for the Autoclave Facility at the Basement Floor of the Research Building (P2–P4 Side), and Wall Panelling Works at Service Rooms in Research Building at IISER Tirupati, Yerpedu.	10 Days	12.11.2025	18.11.2025 at 03:00 p.m.	18.11.2025 at 03:30 p.m.

Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>

TERMS AND CONDITIONS

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Applicants quoting for this work should be a registered “**Civil Contractor**” in CPWD/ AP state PWD/ MES/ Railways/ Autonomous bodies, or an agency with valid GST registration and should have executed Civil works in any government organizations or reputed institutes. The proof of the work experience should be submitted along with the quotation, without the proof of work experience the bids will be summarily rejected.
- 3) **Agency must visit the site before quoting the NIQ to understand the Scope of Work.**
- 4) Time period for completion of work shall be **10 (Ten) Days** from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on engineering@iisertirupati.ac.in or submit to the IISER Tirupati office in hard copy on all working days before a day of the submission date of quotation.
- 5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on or before 3 PM on 18.11.2025. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super sealing the name of work. Quotations will be opened on the same day i.e., 18.11.2025 at 3 PM in the presence of bidder or their

V. Srinivas Kumar



authorized representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons.

- 6) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.
- 7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) **Security deposit @ 2.5 %** shall be recovered at source and refunded after satisfactory completion of **DLP of (12) Twelve months**.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/IS specification is not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.

V. Srinivasan 12/11/24

Executive Engineer (E), IISER Tirupati
On behalf of Director IISER, Tirupati



Copy to:

1. The Registrar, IISER Tirupati.
2. Joint Registrar F & A.
3. Assistant Engineer Civil.

SCHEDULE OF QUANTITIES

Name of the Work: Provision of RO Water Line Connection for the Autoclave Facility at the Basement Floor of the Research Building (P2–P4 Side), and Wall Panelling Works at Service Rooms in Research Building at IISER Tirupati, Yerpedu.

S.No	Description of Item	Units	Qty	Rate	Amount
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, testing of joints complete as per direction of Engineer in Charge				
1.1	25 mm nominal dia Pipes	meter	45		
1.2	20 mm nominal dia Pipe	meter	60		
2	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc., wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge.	sqm	40		
3	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :				
3.1	25mm nominal dia	nos	2		
4	Providing and Fixing Angular stop cock with Valve flange of approved quality ,High and low pressure (Items Should be from approved Make list)				
4.1	20mm nominal dia	nos	3		
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	sqm	380		

Handwritten signature



S.No	Description of Item	Units	Qty	Rate	Amount
6	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.	sqm	380		
7	Supplying and installation of moisture resistant/fire resistant cement board as per standard sizes fixed with self-drilling / tapping screws. Screws shall be of counter sunk rib head of 1.60mm to 4 mm thick or 8 to 10 gauge of length varying from 25 to 45 mm				
7.1	Cement Fiber Board 6 mm thick as per IS 14862:2000 of type B (High pressure Steam Cured)	sqm	262		
Total(Rs.)					

Total Amount in Words:

Note: - Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

V. R. G. Rao

Executive Engineer (E), IISER Tirupati
 On behalf of Director IISER, Tirupati
 (To be filled by the Agency)



Signature of the bidder :
Name of the Agency :
Mobile Number & E-mail ID :
Correspondence Address :

List of Approved Makes:

S.no	Item/ Material	Approved Makes
1	CPVC Pipes	Supreme, Ashirvad, finolex, Astrol
2	Cement Fiber Board	Bison, Ramky, Vishaka or Equivalent

Note: Material to be used for the above work should be reputed make. Agency should take approval from the Engineering In charge before procuring the material.