

NIQ No: 10/IISER/Tirupati/NIQ/2026-27

Date: 15.07.2026

NOTICE INVITING QUOTATION

Item rate sealed quotation are invited by the undersigned on behalf of Director IISER Tirupati for the following work.

Sl. No	Name of Work	Time period of contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1	External development and miscellaneous repair works in Young scientist lab and Weather station at IISER Tirupati campus, Yerpedu.	28 Days	15.07.2026	22.07.2026 at 03:00 p.m.	22.07.2026 at 03:30 p.m.

Quotation can be obtained from IISER Tirupati website <http://www.iisertirupati.ac.in/tenders/>

TERMS AND CONDITIONS

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Applicants quoting for this work should be a registered “**Civil Contractor**” in CPWD/ AP state PWD/ MES/ Railways/ Autonomous bodies, or an agency with valid GST registration and should have executed similar works in any government organization. The proof of the similar work experience should be submitted along with the quotation, without the proof of similar work experience the bids will be summarily rejected.
- 3) **Agency must visit the site before quoting the NIQ to understand the Scope of Work.**
- 4) Time period for completion of work shall be **28 (Twenty-Eight) Days** from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on engineering@iisertirupati.ac.in or submit to the IISER Tirupati office in hard copy on all working days and before one day of the submission date of quotation.
- 5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on and before 3 PM on 22/07/2026. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day i.e., 22/07/2026 at 3.30 PM in the presence of bidder or their authorized



Signature of Agency

representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons/conditions.

- 6) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.
- 7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) **Security deposit @ 2.5 %** shall be recovered at source and refunded after satisfactory completion of **DLP of (12) Twelve months**.
- 10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/IS specification is not available.
- 11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 12) The Contractor should submit computerized measurement book for verification and billing after competition of the work.



Executive Engineer (E), IISER Tirupati

On behalf of Director IISER, Tirupati



SCHEDULE OF QUANTITIES

Name of the Work: External development and miscellaneous repair works in Young scientist lab and Weather station at IISER Tirupati campus, Yerpedu

S.No.	Description of Item	Units	Qty	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	150.00		
2	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	sqm	180.00		
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
3.1	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	kg	200.00		
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
4.1	All kinds of soil.	cum	15.00		
5	Providing and laying factory made Precast concrete solid blocks of 200 mm thickness of grade M10 made of C&D waste from approved manufacturer in superstructure above plinth level up to floor V level.				
5.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	12.00		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.				
6.1	1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	12.00		
7	Centering and shuttering including strutting, propping etc. and removal of form work for :				
7.1	Foundations, footings, bases for columns.	sqm	13.00		
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level.				

V. H. S. R.



S.No.	Description of Item	Units	Qty	Rate	Amount
8.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	8.50		
9	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design.				
9.1	With common burnt clay F.P.S. (non- modular) bricks of class designation 7.5	each	1.00		
10	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. Complete.	sqm	342.00		
11	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.				
11.1	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	sqm	180.00		
12	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade.				
12.1	Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface.	sqm	342.00		
13	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade.				
13.1	One or more coats on old work.	sqm	20.00		
14	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	sqm	105.00		
15	Excavating, supplying, stacking and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in foundation trenches, plinth, sides of foundation etc. complete for all lift.	cum	15.00		

S.No.	Description of Item	Units	Qty	Rate	Amount
16	Constructing brick masonry circular manhole 1.22 m internal dia at bottom and 0.56 m dia at top in cement mortar 1:4 (1 cement :4 coarse sand) inside cement plaster 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement foundation concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) and making necessary channel in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement, all complete as per standard design 1.68 m deep with SFRC Cover and frame (heavy duty HD-20 grade designation) 560 mm internal diameter conforming to I.S. 12592, total weight of cover and frame to be not less than 182 kg. fixed in cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) including centering, shuttering all complete. (Excavation, foot rests and 12 mm thick cement plaster at the external surface shall be paid for separately)				
16.1	With common burnt clay F.P.S. (non- modular) bricks of class designation 7.5	each	5.00		
17	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
17.1	300 mm dia. R.C.C. pipe	m	15.00		
18	Providing, laying & jointing in position Double Wall Corrugated(DWC) perforated HDPE pipes conforming to IS16098(Part2):3013 Structured-Wall plastics piping systems for Non- Pressure drainage and sewerage and suitable for the respective working pressures (SN8) with simple push fit joints with Elastomeric sealing Ring for online system or with extra couplers, accessories e.g. Couplings, tees, bends, reducers, flanged tail pieces etc. jointing as per manufacturers' instruction excluding trenching and refilling etc. : External work (End caps, T or Y Joints and couplers paid separately) NOTE: All joints in the drains and connections between the laterals and main drains shall be made using purpose-made or otherwise approved sealed junctions of appropriate size.	m	85.00		
19	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of	cum	2.00		

S.No.	Description of Item	Units	Qty	Rate	Amount
	unserviceable material within 50 metres lead as per direction of Engineer - in- charge.				
20	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	cum	11.00		
21	Hiring of manpower for material shifting for 8 hours. Rate is inclusive of all taxes nothing extra shall be paid.	Nos	60.00		
	Total Amount(Rs.)				

Total Amount in Words:

Note: - Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

Vergleichsraum ist 12/26.

Executive Engineer (E), IISER

On behalf of Director IISER, Tirupathi

(To be filled by the Agency)



Signature of the bidder :

Name of the Agency :

Mobile Number & E-mail ID :

Correspondence Address :