भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान तिरुपति
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI
(An Autonomous Institution of Ministry of Education, Govt. of India)
Srinivasapuram-Jangalapalli Village, Panguru (G.P) Yerpedu Mandal,
Tirupati, Andhra Pradesh – 517 619.

NIQ No: 18/IISER/Tirupati/NIQ/2026-27 Date: 07/11/2026

NOTICE INVITING QUOTATION

Item rate sealed quotation are invited by the undersigned on behalf of Director IISER Tirupati for the following work.

S. No	Name of Work	Time period of contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1	Supplying and Laying of Street light cables including Earthing system and Associated Civil works at Academic and Residential Zones, IISER Tirupati Campus, Yerpedu.	**14 Days**	07.11.2026	13.11.2026 at 03:00 p.m.	13.11.2026 at 03:30 p.m.

Quotation can be obtained from IISER Tirupati website http://www.iisertirupati.ac.in/tenders/

TERMS AND CONDITIONS

1) No advance payment shall be made by IISER Tirupati.
2) Applicants quoting for this work should be a registered "**Electrical Contractor**" in CPWD/ AP state PWD/ MES/ Railways/ Autonomous bodies, or an agency with valid GST registration and should have executed Electrical works in any government organization. The proof of the work experience should be submitted along with the quotation, without the proof of work experience the bids will be summarily rejected.
3) **Agency must visit the site before quoting the NIQ to understand the Scope of Work.**
4) Time period for completion of work shall be **14 (Fourteen) Days** from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on engineering@iisertirupati.ac.in or submit to the IISER Tirupati office in hard copy on all working days before a day of the submission date of quotation.
5) All agencies need to submit their quotation in hard copy in a sealed envelope to this office by suitable means on or before 3 PM on 13/11/2026. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) super scribing the name of work. Quotations will be opened on the same day

Signature & Stamp of the Agency

i.e., 13/11/2026 at 3.30 PM in the presence of bidder or their authorized representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons/conditions.

6) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.
7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
9) **Security deposit @ 2.5 %** shall be recovered at source and refunded after satisfactory completion of **DLP of (12) Twelve months**.
10) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/IS specification is not available.
11) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
12) The contractor should submit measurements and abstract sheets to IISER TIRUPATI for the payments within 30 days after completion of the work.

07/11/26

Executive Engineer (E), IISER Tirupati
On behalf of Director IISER, Tirupati

Signature & Stamp of the Agency

SCHEDULE OF QUANTITIES

Name of the Work: Supplying and Laying of Street light cables including Earthing system and Associated Civil works at Academic and Residential Zones, IISER Tirupati Campus, Yerpedu.

S. No	Item Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Supplying of XLPE insulated, heavy duty, aluminium conductor. 1.1KV grade armored cable of the following sizes as required, generally conforming to IS:1554/Part-I/1970.				
1.1	4Cx10 SQMM AR, AL	metre	800		
1.2	4Cx25 SQMM AR, AL	metre	200		
2	Supplying and making end termination with brass compressions gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium cable of 1.1KV grade as required.				
2.1	4Cx16 SQMM AR, AL (28mm)	No's	10		
2.2	4Cx10 SQMM AR, AL (25mm)	No's	60		
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in the existing RCC/HUME/Metal/DWC pipe complete as required.				
3.1	Upto 35sqmm	metre	1000		
4	Supplying and laying 6 SWG G.I. wire at 0.50 Meter below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	metre	1400		
5	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.				
5.1	40 mm dia (OD-40 mm & ID-32 mm nominal)	metre	1000		

Signature & Stamp of the Agency

S. No	Item Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
6	Supply and fixing of IP-65 rated control box for cable termination in street light poles, including necessary clamps, connectors and accessories required for installation on the pole, complete as directed by the Engineer-in-charge.	each	20		
7	Excavation of pits for 6m street light poles, placing in position the precast RCC foundation (to be supplied by IISER Tirupati), backfilling with excavated earth, watering, ramming and consolidation around the foundation, and erection of the 6m street light pole with all required accessories, in true line and level as directed by the Engineer-in-charge. **Note: Street light poles with accessories and precast foundations will be supplied by IISER Tirupati.**	each	20		
				Total Amount Rs.	

Total Amount in Words: _____

Note: - Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

07/11/26

Executive Engineer (E), IISER Tirupati
On behalf of Director IISER, Tirupati
(To be filled by the Agency)

Signature of the bidder :

Name of the Agency :

Mobile Number & E-mail ID :

Correspondence Address :

Signature & Stamp of the Agency

List of Approved makes:

S.no	Item/ Material	Approved Makes
1	Aluminium Armoured Cable	Finolex/Polycab or Equivalent
2	Cable glands	Comet, Peeco or Equivalent
3	Aluminium lugs	Dowells, Jainsons
4	HDPE Pipe	RexPolyextrusion/Tirpura/Plasomatics/Duraline

Note: Material to be used for the above work should be reputed make. Agency should take approval from the Engineering In charge before procuring the material.

